

**East Midlands Gateway
Phase 2 (EMG2)**

Document DCO 6.7F/MCO 6.7F

ENVIRONMENTAL STATEMENT

Technical Appendices

Appendix 7F

Monitoring Equipment

October 2025

07

The East Midlands Gateway Phase 2
and Highway Order 202X and The East Midlands Gateway
Rail Freight and Highway (Amendment) Order 202X

[SEGRO.COM/SLPEMG2](https://segro.com/slpemg2)

SEGRO

Appendix 7F

Monitoring equipment

Class 1 Sound Level Meters used:

Survey Location	Dates of Survey	Type	Serial No.	Date of last lab calibration (prior to survey)
L1	04/05/22 – 12/5/22	Larson Davis LxT	3318	03/08/21
L2	04/05/22 – 12/5/22	Larson Davis LxT	3326	17/12/20
L3	12/05/22 – 20/05/22	Larson Davis LxT	3316	18/03/21
L5	04/05/22 – 12/5/22	Larson Davis LxT	3316	18/03/21
L6	18/11/24 – 22/11/24 25/11/24 – 03/12/24	Larson Davis 831	4096	27/03/23
L7	18/11/24 – 03/12/24	Larson Davis LxT	7082	29/04/24
L8	18/11/24 – 03/12/24	Larson Davis LxT	7080	24/04/24
S1	04/05/22 12/05/22	Larson Davis LxT	3317	18/10/21
S2	04/05/22 12/05/22	Larson Davis LxT	3317	18/10/21
S3	02/12/24 03/12/24	Larson Davis LxT	7083	20/11/23
S4	02/12/24 03/12/24	Larson Davis LxT	7083	20/11/23

Class 1 Acoustic Calibrators used:

Dates used	Type	Serial No.	Date of last lab calibration (prior to survey)
All 2022 monitoring	Larson Davis CAL200	12197	30/06/21
All 2024 monitoring	Larson Davis CAL200	11097	17/01/24